



JTC

License# 871341

General Contractor

PO BOX 3814

Santa Barbara – California 93130

805.896.5259

[www.JTConstruction805.com](http://www.JTConstruction805.com)

May 23, 2019

## Proposal

Bill Hirsh  
Water Association  
5599 West Camino Cielo  
Santa Barbara, CA 93105-4007

We hereby submit the following specifications and estimates for:

- ❖ To install one concrete retaining wall for road base DG for 2 water tanks.
- ❖ Dirt pad needs to be prepared and leveled. In order for JTC to install one pad 12' x 24', 288 square feet. The pad will be made of one CMU block high with one footing below roughly 8" wide 10" deep. Concrete footing for CMU blocks to be set in 8"x16" CMU block one row tall with 3 pieces of #4 rebar in footing and CMU block to tie all concrete structural together. There will be 2 reliefs in the pad that are 24"x24" for draining of the pad.
- ❖ We will have 1 layer of 4 mil plastic on top of natural soil with one layer of yellow sand 2 inches thick 6" of DG (Decomposed Granite) compacted every 2"

We propose to furnish material and labor to complete the above specifications, for the sum of:

Option 1) Total for 1 row tall of CMU block \$2400.00

Option 2) Total for 2 rows tall of CMU block \$3875.00

To grade and dig footings for pad \$2500.00

Grand total for option 1; \$4900, Grand total for option 2; \$6275

Payment and deposit are to be made as follows:

Deposit of \$1000 to start, remainder to be paid day of completion.

**Contractor's Signature:** \_\_\_\_\_

**Owner's Signature:** \_\_\_\_\_ **Date:** \_\_\_\_\_

Acceptance of Proposal: The above price, specifications and conditions are satisfactory and are hereby accepted. You are authorized to do the work as specified.